

Steps of Construction and Site Management.

Engr.Md. Reaz Uddin Sarker
Senior Research Engineer
HBRI.



Building Structures

- Load Bearing Wall Structure
- Non- Load Bearing Wall Structure / Frame Structure



Organ/ Parts of a Building Structure

- **Foundation/Footing**

- **Column**

- Short Column
- Long Column

- **Beam**

- Grade Beam
- Floor Beam
- Roof Beam

- **Slab**

- Roof Slab
- Floor Slab

- **Type of Slab**

- One Way
- Two Way
- Flat Plate
- Flat Slab
- Waffle Slab

- **Lintel**

- **Under Ground Water Reservoir**

- **Septic Tank**

- **Soak Well**

- **House Top Water Tank**

- **Wall**

- 10" Wall
- 5" Wall
- 3" Wall
- Cavity Wall



• Foundation/Footing



• Column



• Beam



• Slab



• Lintel



• Wall



Selection of Land

Topography:

- Hilly Land
- Ditch/Pond
- ✓ Plane Land

Location of Land

Service Facilities Available:

Water Supply

Electric Supply

Sewerage Lines

Communication Facilities

Near by Primary School

Shape of Land

- ✓ Rectangular
- ✓ Square
- Trapezoidal
- Triangular




Pre-construction Stage

Professional Responsible

Planning of the house (Architectural design)	An Architect or a group
Soil testing	Foundation Engineer (Civil)
Structural design	Structural Engineer (Civil)
Electric design	Electrical Engineer
Service facilities design	Environment Engineer
Quantity analysis of materials and Costing	Diploma Engineer (Civil)

[illegible]

Structural design



Site Preparation

- Selection of Contractors / Working Gang
- Labor Shed / Temporary Site Office
- Arrangement of Water and Electric Supply
- Arrangement of Construction Material
- Arrangement of Equipments
- Arrangement for Disposal of Waste Material



Construction Start

- Giving layout
- Trench cutting
- Foundation casting
- Column casting up to grade beam
- UG Reservoir casting
- Grade beam casting
- Stair casting
- Column casting (ground floor)
- Floor beam and slab casting





Giving layout
Trench cutting



Foundation casting



Column casting up to grade beam

Steps of Foundation Casting



- Brick soling
- 3" CC casting upon soling
- Construction of wall foundation or Laying reinforcement for footing casting with appropriate shuttering arrangement
- Construction of water reservoir
- Filling of sand into the boundary area of footing and apply appropriate compaction

Construction of Columns

- Rod Binding from foundation level
- Shuttering arrangement
- Pouring concrete and proper compaction
- Curing to be ensured

Construction of Lintels

- Centering for lintels, sunshade, drop walls and cantilever slabs
- Rod binding for casting





Construction of Columns



Construction of Lintels



Construction of Beams and Slab Monolithically



- Centering, shuttering and propping to be ensured
Form work to be arranged for beams and slab casting monolithically

At first beam to be cast then slab to be cast

After rod binding, laying electrical duct and sanitary fittings and approval of site engineer casting to be started
Curing to be done for at least 28 days




Construction of Beams



Slab Monolithically





SPECIAL
REINFORCEMENT
AT EXTERIOR
CORNER OF
A BEAM
SUPPORTED TWO
WAY SLAB



Table





After completion of Curing

- Centering to be removed
- Wall to be constructed
- Fitting of doors and windows frame
- Plaster the wall
- Construction of septic tank
- Construction of sanitary pits and laying of underground RCC pipe outer surface of the wall



Floor Finishing

- Soling is prepared upon compacted sand filled trenches for ground floors
- Water-proof and heat-proof roof to be constructed and then it should be cured
- Mosaic finishing and curing
- Tiles laying in bathroom
- Construction of boundary wall
- Casting of entrance road and collapsible gate fitting



Finishing Works

- Fittings for kitchen
- Window and door fittings
- Pan, shower and basin adjustment in bathroom
- Establishing of electric line
- Fitting of hand rails of stairs
- White wash or distempering the wall
- Varnishing of wooden frames
- Electric Fixtures like (fans, lights)
- Vegetation and plantation



Thank You

